



- 1 ROOF PANEL
- 2 PANEL CLIP WITH FASTENER. INSTALL 2 CLIPS AT EAVE TYPICAL
- 3 ONE LAYER OF 30 LB. FELT STRIPPED IN OVER TERMINATION FLSG
- 4 PLYWOOD SHEATHING
- 5 10x1" PANCAKE HEAD WOOD SCREW, INSTALL 12" O.C. STAGGERED
- 6 CUT BACK VERTICAL LEGS AND FIELD FORM PANEL AROUND OFFSET HEM
- 7 TERMINATION FLASHING, 4" END LAPS WITH CONT. CAULK AT LAPS
- 8 CONTINUOUS BEAD OF SEALANT BETWEEN FELT AND FLASHING
- 9 ADHERED EPDM MEMBRANE, EXTEND MIN. 24" UNDER ROOF PANELS